

BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineer

Yelahanka Division

B.B.M.P. Bengaluru - 64

No.EEYJK/D/E-PWT/2015-16 Dated: 04-01-2016

APPROVED TENDER SCHEDULE -'B'

Item No: 09

Name of Work:- Construction of drain at Surabhi layout, Shivanahalli and Basveshwaraanaga in ward No-01 of Yelahanka Sub Division.

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri T C SHANKARAPPA	
				Rate	Rate in Words
1	KSRRB 300-1: Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH chapter 3. No. 141/ Item No. 19 1/ PWD SR 2015-16	Cum	90.00	79.00	Rupees seventy nine only
2	KSRRB 2-2.1: earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with load upto 50m, after breaking of clods complete as per specifications, specification, No. KBS 2.1(a)/2.3.5, No. 5/ Item No. 2.3/ PWD SR 2015-16	Cum	300.00	183.00	Rupees one hundred eighty three only
3	KSRRB 100-1 Loading and unloading of stone aggregates / sand/ kanker/ Moorum /soil KSRRB M100-1 Picking upper al loading with front end loader dumping turning for return trip excluding time for hauled and return trip complete as per specification Item No. 17.1 page 130 and KSRRB M-100.4.1 cost of haulage excluding bedding and unloading MORTH to a distance of 4.00 K/M (Item No. 17.4 Page 130 (SR 2015-16)	Cum	390.00	81.00	Rupees eighty one only
4	KSRRB-4-12: Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement at 220kg/sq. with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.466cum machine mixed, concrete laid in layers not exceeding 15cm, thick, well compacted, in foundation and plinth, including cost of all materials, labour, H.O.M of machinery, curing complete as per specifications. Specification No. KBS 4.1.4.2, No. 12/ Item No. 4.2/ PWD SR 2015-16	Cum	45.00	4975.00	Rupees four thousand nine hundred seventy five only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri T C SHANKAR 2024	
				Rate	Rate in Words
5	KSRB 4.2.2: Providing and laying in place of plain cement concrete of mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregates @ 0.460 cum with superplastic @ 3lts conforming to IS 9103-1998 Reformed machine mixed exceeding 15cms thick vibrated for all works in foundation plinth and ground floor level for roof slabs, staircases, inlets, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc. including cost of all materials, labour H.O.M of machinery, cutting complete as per specifications. Specification No. KBS 4.1.4.6, No. KBS 4.1.4.6, No. 13/ Item No. 4.31/ PWD SR 2015-16	Cum	99.00	5988.00	Rupees five thousand eight hundred eighty eight only
6	KSRB 4.3.2 providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, H.O.M of machinery complete as per specifications. Specification No. KBS 4.6.3 Page No. 17/ Item No. 4.46/ PWD SR 2014-15	Qlt.	60.39	6632.00	Rupees six thousand six hundred thirty two only
7	KSRB 4.6.4: Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, attached pilasters, buttresses, plinth and string course including cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 Page No. 15/ Item No. 4.31/ PWD SR 2015-16	Sqm	720.00	291.00	Rupees two hundred ninety one only
8	RCC Precast covering slab for drain (10cm thick)	Sqm	253.80	1423.00	Rupees one thousand four hundred twenty three only

Signature
Signature of the Contractor

Signature
Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.